

**CITY OF PEACHTREE CORNERS**  
**CONSTRUCTION SITE PLAN INSPECTION PROCEDURES**  
(MARCH 2015)

- Step 1:** Upon arrival at a job site, the superintendent is notified of the inspector's presence on the site.
- Step 2:** The inspector walks the entire job site, including active work areas and stabilized areas. If any deficiencies are found, the inspector will include his/her findings on the *Land Disturbance Permit Site Check List* form and document with photographs.
- Step 3:** Turbidity samples are only collected if a discharge is present during inspection. If a discharge is found that exceeds the approved limits for the job site, a copy of the inspection form is given to the job superintendent or their designee.
- Step 4:** If the sample is within the approved limits, however, other deficiencies are found, a copy of the inspection form is given to the job superintendent or their designee.
- Step 5:** Corrective actions are to be made within 48 hours of notification. In serious situations immediate attention is required.
- Step 6:** Follow up inspections are made to ensure that corrections have been made and working properly.
- Step 7:** Copies of the inspection report and detailed photographs of deficiencies are placed in the file for that project.

FOR MORE INFORMATION CONTACT  
THE CITY OF PEACHTREE CORNERS  
147 TECHNOLOGY PARKWAY  
SUITE 200  
PEACHTREE CORNERS, GA 30092  
PHONE: 678-691-1200