



## City of Peachtree Corners Town Green Construction Project

RFP #18-004

Addendum #4

---

**May 2, 2018**

The following changes, additions or deletions shall be made to the following document(s); all other conditions remain the same. Each Bidder shall be responsible for ascertaining, prior to submitting a Bid, that they have received all issued Addenda.

1389 Peachtree Street, NE  
Suite 200  
Atlanta, GA 30309

Phone: 404.873.6730  
[www.tsw-design.com](http://www.tsw-design.com)

*Principals:*

William Tunnell  
Jerry Spangler  
Thomas Walsh  
Caleb Racicot  
Adam Williamson  
Bryan Bays  
Heather Hubble

*Associates:*

Rebekah Calvert  
Ben Woodrow Giles  
David Lintott  
Alex Fite-Wassilak  
Lionel Johnson  
Sarah McColley  
Laura Richter

1. Responses to Bidding RFIs on pg. 2.

## **Bidding RFI Questions**

Please see TSW's responses in red below.

**Date Received: Wednesday, May 2<sup>nd</sup>, 2018**

1. See page L-7.04. Detail 1 calls out a 4" compacted base of 57 stone. However, the details clearly shows a 6" base. Please clarify.  
All walls should have a 6" compacted base, #57 stone.
2. See page L-7.05. Note #5 calls for glass to be 3/8" thick. However, several of the details below that call for 2" black fire glass. Please confirm which is correct.  
The glass should be 3/8" thick, and applied to a depth of 2".
3. See page L-7.06. Note #5 call for metal to be aluminum. However several of the details below that call for stainless. Please clarify.  
Fire columns' metal base should be stainless steel.
4. See page L-7.07. Note #3 calls for 4000k LED lights. However, the enlarged light fixture detail calls for 400k. Please clarify.  
LED light to be 4000k
5. See page L-7.10. Details for non-visible CIP concrete walls and concrete sonotube show 57-stone (no thickness noted). No other details show 57-stone under the deck. Also, L-7.11 isn't really clear on full extent of location. Is the stone required under the entire deck?  
The sonotubes are not required to have a compacted aggregate (#57 stone) base under them as long as the subgrade beneath the sonotube can be compacted to 95% standard proctor. The concrete walls should have a 6" compacted aggregate base (#57 stone).  
  
A 4" gravel base underneath the entire deck should be included in the bid. This is to help with the drainage and erosion underneath the deck.

**All other terms & conditions remain unchanged.**

**End of Bidding – Addendum #4**